
ltem	Description		
1	Aerona ASHP		
2	Flexible hose & Isolation valve ¹		
3	Grant volumiser or Low loss header*** (optional)		
4	Anti-Vibration Mounts ²		
5	Flow sensor ¹		
6	Grant Mag One magnetic filter kit ²		
7	Wiring centre ¹		
8	Touchscreen display ¹		
9	Room thermostat		
10	Automatic air vent		
11	Cylinder immersion heater		
12	DHW cylinder		
13	Immersion heater relay ²		
14	Drain point		
15	Removable filling loop ²		
16	Double check valve ²		
17	Pressure gauge ²		
18	Expansion vessel ²		
19	Tundish		
20	Pressure relief valve ²		
21	UFH pump downstairs		
22	UFH manifold Downstairs		
23	3-Port diverter valve ²		
24	3-Port mixing valve Downstairs ³		
25	Water temperature sensor ¹		
26	Outdoor weather sensor ¹		
27	UFH pump upstarisa		
28	UFH manifold Upstairs		
29	3-Port mixing valve Upstairs ³		
¹ Supplied with the HPIDR32SMART* Smart Controller Kit *Outputs available: 6,10,13 & 17kW ² Supplied with HPIDR32PACKQ ³ One 3-Port mixing valve supplied in PackQ			

IMPORTANT

The below diagram shows the Flow (outlet) and Return (inlet) connection positions for HPID6R32BODY models ONLY.



**Compression elbow c/w air vent (supplied with HPIDVOL30EXT6)



Scale: NTS Paper Size: A3

! NOTE !

! NOTE!

***30L external volumiser is available as an optional component where

26

2

(1)

(2)

IMPORTANT

2

· · · · ·

(3

For positions of the Flow (outlet) and Return (inlet) connections on HPID10R32BODY, HPID13R32BODY

there is insufficient system volume (HPIDVOLEXT30).

(2)


and HPID17R32BODY models, see above.

(23)

Port A

(5)

Please refer to the Aerona ASHP installation instructions for details of the flow and return connections at the heat pump.




! NOTE !

For additional heater support from Grant External Volumiser, Refer to Grant Aerona Smart Controller installation manual and Schematics HPCS-BUHS and HPCS-BUHE.

! NOTE !

This system schematic should be read in conjunction with the Grant Aerona Smart Control installation instructions and wiring diagram HPCS-Q002ER32.

Status: Rev Da This drawing and its or Frankland Road, Blagr



Project Title: Grant Aerona Smart Controls							
Installati							
W-Plan F							
UFH downstairs & upstairs - Open Loop Thermostatically controlled (Pump Blockage on) HW priority & Legionella Protection from wiring centre (System schematic)							
				Drawing Set: Aerona	Dwg. No:		
				System	Schematics	HPCS-Q002SR32	
Status: Approved	Revision: 0.2						
Rev Date: 21/06/24	Drawn By: AC&DB	Checked By: NS					

nt is subject to copyright. Use other than for its original intended purpose must be arranged with an employee of Grant UK Ltd. Industrial Estate, Swindon, SN5 8YU, tet; 01380 736920